



**NOTES:**

1. SCARIFY SUBGRADE TO A MIN. DEPTH OF 6" BEFORE INSTALLATION.
2. IF SIDE SLOPES STEEPER THAN 3:1 ARE REQUIRED, THEY MUST BE CONSTRUCTED IN ACCORDANCE WITH CITY PLANTING SPECIFICATIONS.
3. TREES AND PLANTINGS SHALL BE INSTALLED IN ACCORDANCE WITH DESIGN PLANS AND SPECIFICATIONS.
4. BOTTOM OF BIOSWALE SHALL BE A MIN. OF 2'-0" ABOVE SEASONAL HIGH WATER TABLE AND BEDROCK AS DETERMINED BY GEOTECHNICAL INVESTIGATION OR APPROVED SOIL EVALUATION.
5. INFILTRATION SUMP SHALL BE SIZED TO MEET THE RECHARGE AND/OR WATER QUALITY VOLUME REQUIREMENTS OF THE STORMWATER HANDBOOK.



**Public Works Department  
 Engineering Division**  
 1 CITY HALL SQUARE, ROOM 710  
 BOSTON, MA 02201  
 (617) 635-4968

**BIOSWALE SECTION**

**DATE OF ISSUE:**  
 DECEMBER 2024

**SCALE:** N.T.S.

**DETAIL NO.**

G.321