



PLANTING NOTES:

- 1) ALL PLANTINGS REQUIRE A 2 YEAR WARRANTY.
- 2) HOLE SHALL BE EXCAVATED A MINIMUM OF TWICE THE DIAMETER OF THE ROOTBALL, ONLY AS DEEP AS THE ROOTBALL, AND SHALL HAVE SLOPED SIDES. BACKFILL THE PLANTING HOLE WITH PLANTING SOIL MIX IN LAYERS NOT TO EXCEED 6" AT ONE TIME. LIGHTLY TAMP OR THOROUGHLY WATER IN EACH LAYER OF SOIL THAT IS PLACED AROUND THE ROOTBALL TO THOROUGHLY SETTLE THE SOIL. CONTINUE BACKFILLING WITH THE NEXT LAYER OF SOIL UNTIL THE PLANTING MIX LEVEL IS AT THE LEVEL THAT THE PLANT WAS PREVIOUSLY GROWN. WATER IN AGAIN AND ADJUST SOIL LEVEL TO COMPENSATE FOR ANY SETTLEMENT THAT MAY OCCUR.
- 3) INSTALL 20 GALLON CAPACITY WATERING BAG DIRECTLY AROUND STAKE AND OVER ROOTBALL. EACH TREE SHALL HAVE ITS WATER BAG FILLED WITH 20 GALLONS OF WATER PER WATERING. TREES SHALL BE WATERED ONCE A WEEK FOR THE FIRST FOUR (4) WEEKS AFTER PLANTING. AFTER THE FIRST FOUR (4) WEEKS ALL TREES MUST BE WATERED ON A BI-WEEKLY BASIS (ONCE EVERY 2 WEEKS). TREES SHALL BE WATERED FOR THE FIRST TWO (2) YEARS POST PLANTING FROM APRIL 1ST THROUGH SEPTEMBER 30TH.
- 4) APPLY FERTILIZER TO PLANTING SOIL MIX AT TIME OF PLANTING AS SPECIFIED IN CONTRACT.



**Public Works Department
Engineering Division**

1 CITY HALL SQUARE, ROOM 710
BOSTON, MA 02201
(617) 635-4968

STORMWATER TREE PLANTING

**DATE OF ISSUE:
DECEMBER 2024**

SCALE: N.T.S.

DETAIL NO.

G.362