GENERAL

The work consists of the furnishing, placing and compacting Washed River Stone at the locations and dimensions specified on the Plans and as required by the Engineer.

Submittals

The Contractor shall submit a minimum five (5) gallon sample of stones to the Engineer for review and approval prior to ordering the material.

MATERIALS

Washed river stone shall have rounded, tumbled edges and shall be of various shades of gray, brown, or tan. Stone shall be between 2 and 8 inches in diameter. All fines shall be screened from the aggregate. The material shall be free of organic and inorganic debris and trash.

CONSTRUCTION METHODS

Install the non-woven geotextile fabric per detail (if applicable), either on the subbase and sides or encasing washed river stone.

The stone shall be placed to the line and grade as shown on the Plans or as directed by the Engineer.

METHOD OF MEASUREMENT

Washed River Stone will be measured for payment by the cubic yard, complete in place.

BASIS OF PAYMENT

Washed River Stone will be paid for at the Contract unit price per cubic yard, which price shall include all labor, materials, equipment, and incidental costs required to complete the work.

Excavation will be paid for separately under Item 120.1, Excavation.

Non-Woven Geotextile Fabric will be paid for separately under item 698.3, Non-Woven Geotextile Fabric.