

<u>ITEM 797.20X</u>	<u>TREE 2-2.5 INCH CALIPER</u>	<u>EACH</u>
<u>ITEM 797.25X</u>	<u>TREE 2.5-3 INCH CALIPER</u>	<u>EACH</u>
<u>ITEM 797.30X</u>	<u>TREE 3-3.5 INCH CALIPER</u>	<u>EACH</u>
<u>ITEM 798.10X</u>	<u>SHRUB #1 CONT.</u>	<u>EACH</u>
<u>ITEM 798.20X</u>	<u>SHRUB #2 CONT.</u>	<u>EACH</u>
<u>ITEM 798.30X</u>	<u>SHRUB #3 CONT.</u>	<u>EACH</u>
<u>ITEM 799.04X</u>	<u>PERENNIAL 4 INCH POT</u>	<u>EACH</u>
<u>ITEM 799.10X</u>	<u>PERENNIAL #1 CONT.</u>	<u>EACH</u>
<u>ITEM 799.20X</u>	<u>PERENNIAL #2 CONT.</u>	<u>EACH</u>
<u>ITEM 799.80X</u>	<u>PERENNIAL PLUG</u>	<u>EACH</u>
<u>ITEM 799.90X</u>	<u>PERENNIAL BULB</u>	<u>EACH</u>

The work under these items shall conform to the applicable requirements of Subsection 771, PLANTING TREES, SHRUBS AND GROUNDCOVER, of the MassDOT Standard Specifications.

As indicated on the Plans, plantings are schematic and shall be staked out in the field and confirmed with the Landscape Architect and the City.

Plant substitutions must be approved by the Landscape Architect prior to ordering plants.

METHOD OF MEASUREMENT

Items 797.20X thru 799.90X will be measured for payment by the each, complete in place.

BASIS OF PAYMENT

Items 797.20X thru 799.90X will be paid for at the Contract unit price per each, which price shall include all labor, materials, equipment, and incidental costs required to complete the work. No separate payment will be made for excavation, furnishing and installing backfill material, testing and amending planting soil as necessary, and disposing of surplus material, but all costs in connection therewith shall be included in the Contract unit price bid.